

CUB/M2 - NBR 12721:2006 - JANEIRO/2009
Composição

Valores em R\$/m²

Valores em %

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	465,01	518,01	500,22	328,34
Mão-de-obra	303,51	254,19	239,13	206,88
Desp. Administ.	93,01	24,73	22,25	23,07
Equipamento	2,87	2,78	2,91	1,45
Total	864,40	799,71	764,52	559,75

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	53,80%	64,77%	65,43%	58,66%
Mão-de-obra	35,11%	31,79%	31,28%	36,96%
Desp. Administ.	10,76%	3,09%	2,91%	4,12%
Equipamento	0,33%	0,35%	0,38%	0,26%
Total	100%	100%	100%	100%

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	506,58	506,13	453,45	448,49
Mão-de-obra	410,76	363,44	326,03	313,29
Desp. Administ.	87,33	104,72	48,31	39,98
Equipamento	0,20	0,04	3,90	3,72
Total	1004,87	974,32	831,69	805,48

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	50,41%	51,95%	54,52%	55,68%
Mão-de-obra	40,88%	37,30%	39,20%	38,89%
Desp. Administ.	8,69%	10,75%	5,81%	4,96%
Equipamento	0,02%	0,00%	0,47%	0,46%
Total	100%	100%	100%	100%

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	751,29	640,24	614,38
Mão-de-obra	445,62	345,53	388,02
Desp. Administ.	82,56	56,97	49,42
Equipamento	0,25	3,68	5,59
Total	1.279,72	1.046,42	1.057,40

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	58,71%	61,18%	58,10%
Mão-de-obra	34,82%	33,02%	36,70%
Desp. Administ.	6,45%	5,44%	4,67%
Equipamento	0,02%	0,35%	0,53%
Total	100%	100%	100%

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	517,40	434,85	587,31
Mão-de-obra	362,95	328,24	437,27
Desp. Administ.	64,73	51,10	57,32
Equipamento	6,59	4,18	6,48
Total	951,68	818,38	1088,39

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	54,37%	53,14%	53,96%
Mão-de-obra	38,14%	40,11%	40,18%
Desp. Administ.	6,80%	6,24%	5,27%
Equipamento	0,69%	0,51%	0,60%
Total	100%	100%	100%

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	591,41	511,17	689,34
Mão-de-obra	366,45	337,67	450,06
Desp. Administ.	64,74	51,10	57,32
Equipamento	6,59	4,22	6,43
Total	1.029,19	904,15	1.203,15

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	57,46%	56,54%	57,29%
Mão-de-obra	35,61%	37,35%	37,41%
Desp. Administ.	6,29%	5,65%	4,76%
Equipamento	0,64%	0,47%	0,53%
Total	100%	100%	100%

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	RP1Q	GI
Material	373,49	271,37
Mão-de-obra	389,27	182,64
Desp. Administ.	-	-
Equipamento	3,66	1,54
Total	766,42	455,55

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	RP1Q	GI
Material	48,73%	59,57%
Mão-de-obra	50,79%	40,09%
Desp. Administ.	0,00%	0,00%
Equipamento	0,48%	0,34%
Total	100%	100%

This document was created with Win2PDF available at <http://www.win2pdf.com>.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.
This page will not be added after purchasing Win2PDF.