

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	461,85	506,38	489,49	321,82
Mão-de-obra	303,51	254,19	239,13	206,88
Desp. Administ.	91,32	24,28	21,85	22,65
Equipamento	2,84	2,75	2,88	1,44
Total	859,51	787,60	753,35	552,79

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	53,73%	64,29%	64,98%	58,22%
Mão-de-obra	35,31%	32,27%	31,74%	37,43%
Desp. Administ.	10,62%	3,08%	2,90%	4,10%
Equipamento	0,33%	0,35%	0,38%	0,26%
Total	100%	100%	100%	100%

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	509,75	504,19	452,04	446,79
Mão-de-obra	410,76	363,44	326,03	313,29
Desp. Administ.	85,74	102,81	47,43	39,25
Equipamento	0,20	0,04	3,86	3,68
Total	1006,45	970,48	829,36	803,01

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	50,65%	51,95%	54,50%	55,64%
Mão-de-obra	40,81%	37,45%	39,31%	39,01%
Desp. Administ.	8,52%	10,59%	5,72%	4,89%
Equipamento	0,02%	0,00%	0,47%	0,46%
Total	100%	100%	100%	100%

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	752,71	638,90	615,52
Mão-de-obra	445,62	345,53	388,02
Desp. Administ.	81,06	55,93	48,52
Equipamento	0,25	3,64	5,52
Total	1.279,64	1.044,01	1.057,58

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	58,82%	61,20%	58,20%
Mão-de-obra	34,82%	33,10%	36,69%
Desp. Administ.	6,33%	5,36%	4,59%
Equipamento	0,02%	0,35%	0,52%
Total	100%	100%	100%

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	516,07	434,24	586,98
Mão-de-obra	362,95	328,24	437,27
Desp. Administ.	63,55	50,17	56,28
Equipamento	6,52	4,13	6,41
Total	949,09	816,79	1086,94

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	54,37%	53,16%	54,00%
Mão-de-obra	38,24%	40,19%	40,23%
Desp. Administ.	6,70%	6,14%	5,18%
Equipamento	0,69%	0,51%	0,59%
Total	100%	100%	100%

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	590,23	511,24	689,83
Mão-de-obra	366,45	337,67	450,06
Desp. Administ.	63,56	50,17	56,28
Equipamento	6,52	4,17	6,36
Total	1.026,76	903,24	1.202,52

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	57,49%	56,60%	57,37%
Mão-de-obra	35,69%	37,38%	37,43%
Desp. Administ.	6,19%	5,55%	4,68%
Equipamento	0,63%	0,46%	0,53%
Total	100%	100%	100%

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	RP1Q	GI
Material	369,42	271,50
Mão-de-obra	389,27	182,64
Desp. Administ.	-	-
Equipamento	3,62	1,52
Total	762,31	455,66

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	RP1Q	GI
Material	48,46%	59,58%
Mão-de-obra	51,06%	40,08%
Desp. Administ.	0,00%	0,00%
Equipamento	0,47%	0,33%
Total	100%	100%

This document was created with Win2PDF available at <http://www.win2pdf.com>.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.
This page will not be added after purchasing Win2PDF.