



## COMPOSIÇÃO DO CUB/m<sup>2</sup> (NBR 12.721:2006 - CUB 2006) MÊS: AGOSTO ANO: 2012

Valores em R\$/m<sup>2</sup>

Valores em %

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	493,63	534,39	510,08	347,39
Mão-de-obra	435,72	365,08	343,42	296,99
Desp. Administ.	142,12	37,79	34,00	35,24
Equipamento	4,33	4,18	4,39	2,19
<b>Total</b>	<b>1.075,80</b>	<b>941,44</b>	<b>891,89</b>	<b>681,81</b>

Item	Projetos-Padrão Residenciais - Baixo			
	R-1	PP-4	R-8	PIS
Material	45,89%	56,76%	57,19%	50,95%
Mão-de-obra	40,50%	38,78%	38,50%	43,56%
Desp. Administ.	13,21%	4,01%	3,81%	5,17%
Equipamento	0,40%	0,44%	0,49%	0,32%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	524,21	508,71	455,34	447,16
Mão-de-obra	591,35	523,19	469,44	451,16
Desp. Administ.	133,44	160,01	73,82	61,09
Equipamento	0,30	0,06	5,88	5,60
<b>Total</b>	<b>1.249,30</b>	<b>1.191,97</b>	<b>1.004,48</b>	<b>965,01</b>

Item	Projetos-Padrão Residenciais - Normal			
	R-1	PP-4	R-8	R-16
Material	41,96%	42,68%	45,33%	46,34%
Mão-de-obra	47,33%	43,89%	46,73%	46,75%
Desp. Administ.	10,68%	13,42%	7,35%	6,33%
Equipamento	0,02%	0,00%	0,59%	0,58%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	759,62	638,20	624,40
Mão-de-obra	641,56	497,35	558,53
Desp. Administ.	126,15	87,04	75,51
Equipamento	0,37	5,55	8,41
<b>Total</b>	<b>1.527,70</b>	<b>1.228,14</b>	<b>1.266,85</b>

Item	Projetos-Padrão Residenciais - Alto		
	R-1	R-8	R-16
Material	49,72%	51,96%	49,29%
Mão-de-obra	42,00%	40,50%	44,09%
Desp. Administ.	8,26%	7,09%	5,96%
Equipamento	0,02%	0,45%	0,66%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	523,16	439,60	590,80
Mão-de-obra	522,76	472,59	629,52
Desp. Administ.	98,90	78,08	87,59
Equipamento	9,93	6,30	9,76
<b>Total</b>	<b>1.154,76</b>	<b>996,57</b>	<b>1.317,67</b>

Item	Projetos-Padrão Comerciais - Normal		
	CAL-8	CSL-8	CSL-16
Material	45,31%	44,11%	44,84%
Mão-de-obra	45,27%	47,42%	47,78%
Desp. Administ.	8,56%	7,84%	6,65%
Equipamento	0,86%	0,63%	0,74%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	598,08	513,80	690,07
Mão-de-obra	527,79	486,09	647,84
Desp. Administ.	98,91	78,08	87,58
Equipamento	9,93	6,35	9,69
<b>Total</b>	<b>1.234,72</b>	<b>1.084,33</b>	<b>1.435,18</b>

Item	Projetos-Padrão Comerciais - Alto		
	CAL-8	CSL-8	CSL-16
Material	48,44%	47,38%	48,08%
Mão-de-obra	42,75%	44,83%	45,14%
Desp. Administ.	8,01%	7,20%	6,10%
Equipamento	0,80%	0,59%	0,68%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>	<b>100,00%</b>

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	Galpão Industrial (GI)	
	RP1Q	GI
Material	411,87	278,34
Mão-de-obra	561,05	262,95
Desp. Administ.	-	-
Equipamento	5,51	2,32
<b>Total</b>	<b>978,43</b>	<b>543,60</b>

Item	Projetos - Padrão	
	Residência Popular (RP1Q)	
	Galpão Industrial (GI)	
	RP1Q	GI
Material	42,09%	51,20%
Mão-de-obra	57,34%	48,37%
Desp. Administ.	0,00%	0,00%
Equipamento	0,56%	0,43%
<b>Total</b>	<b>100,00%</b>	<b>100,00%</b>

COMPOSIÇÃO DO CUB/m<sup>2</sup> - Sinduscon-BA

This document was created with Win2PDF available at <http://www.win2pdf.com>.  
The unregistered version of Win2PDF is for evaluation or non-commercial use only.  
This page will not be added after purchasing Win2PDF.